

Request for Quotations
Tequesta Park Tennis Courts Renovations
2280 S.E. County Line Rd.
Tequesta, FL 33469

RFQ No. PARKS 03-21

Fencing

1. Contractor cut of all of the exterior poles to ground level and saw cut and jack hammer out the center court line posts corner posts & and dispose of all of the existing related chain link fencing and related debris.
2. Contractor will supply and install all equipment, labor, and material to install (540) LF of 10' high, (270) LF of 6' high, and (230) LF of 4' high 9 gauge vinyl coated chain link fencing with (2) 4' high gates and (1) 7 high gate (3) feet wide according to the current Florida Building Code 2021. The colors Green and Black.

Schedule of Values: _____

Premium Pickle ball Net Posts

1. Basic Pickle ball Net Posts: This contractor will supply & install 6 pair(s) of new Douglas Pickle ball external wind Sidewinder powder coated net posts in new net post footers & sleeves. [Additional Information](#)

Schedule of Values: _____

Premium Pickle ball Nets

1. This contractor will supply & install 6 new Douglas tournament pickle ball net(s) #JTN-30 nets which are 3.0mm single ply vinyl coated head band. [Additional Information](#)

Schedule of Values: _____

Premium Tennis Net Posts

1. Basic Tennis Net Posts: This contractor will supply & install 2 pair(s) of new Douglas external wind Sidewinder powder coated net posts in new net post footers & sleeves. [Additional Information](#)

Schedule of Values: _____

Premium Tennis Nets

1. This contractor will supply & install 2 new Douglas professional tennis net #TN-45 net(s). These are tapered 3.5mm with double thick polyester headband. [Additional Information:](#)

Schedule of Values: _____

Premium Court Surfacing With Fiberglass Overlay

1. The court(s) area to be re-surfaced measures approximately 25,992 square feet and will be 2 tennis courts & 6 pickle ball courts. All work provided will be inside the fenced area.
2. Contractor will clean the court(s) surface by either power washing or sanding the court as required.
3. Contractor will grind down all the ridges as required.
4. Contractor will treat all cracks 1/16 or more with various techniques for highest degree of strength.
5. Contractor will install 100% acrylic liquid patch binder with a mixture of Portland cement & sand up to as required to treat depressions more than 1/8" in depth on the playing surface to promote water distribution.
6. Contractor will install (1) coat of Laykold's Acrylic Base Coat Surfacer. This Acrylic Base Coat Resurfacer is a premium quality 100% acrylic when mixed with silica sand, Portland cement and water it provides an excellent acrylic filler coat that provides a 1/16" deep overlay onto the courts surface. This is highly recommended for all old aged out courts.
7. Contractor will install approximately 25,992 of a 2 mm resin coated fiberglass membrane over the entire court surface. The membrane is installed by using a 3' wide sections with a 2" overlap system to ensure seams have proper adhesion using a coat of Laykold's Nusurf Acrylic Resurfacer. Laykold's Nusurf has 800 % more elongation properties than what are competitors use in their application process. This technique is specifically designed for modern fabric and fiberglass crack repair systems.
8. Contractor will install an additional coat of Laykold's Nusurf with a heavy sand texture by squeegee of Laykold's high performance acrylic primer. This application is designed to fully coat the fiber glassed area with texture prior to applying the color coats for follow.
9. After the resurfacing material has been applied and cured this contractor will install 2 coats of Laykold's premium high performance factory textured acrylic color coat system according to the manufacturer's specifications.
10. After the color system has been applied contractor will seal and stripe the lines in a highly textured white paint for 2 tennis court & 6 pickle ball courts.
11. When completed this contractor will reopen the court(s) and dispose of all related material used in a safe and suitable disposal area.

Schedule of Values: _____

Concrete sidewalk & Viewing Areas

1. Contractor will supply all labor and material to install approximately 6200 square feet of 4" thick sidewalk from the existing brick paving along the fence line and connecting to 2 viewing areas measuring approximately 1350 square feet each with a connecting sidewalk.

Schedule of Values: _____

Viewing Bleachers

1. Contractor will supply and install (2) 30 Person (2) rows aluminum bleachers with double foot planks measuring 21' wide x 36' wide.

Schedule of Values: _____

1. **NOTE:**

Please include **insurance info (1 Million listing VOT as additional insurer), W-9, contractors licensed, references, warranty info**, please provide additional information that they feel might be helpful in assisting the Village in determining your ability to perform the required services/work outlined in the "RFQ.").

The following forms are required to be submitted:

- Quote submittal
- ADA Compliancy Statement
- Drug-free Workplace Certification
- Conflict of Interest
- Reference Form

All quotations must be submitted electronically via [DemandStar](#) RFQ must reference RFQ No. PARKS 03-21

For more information: Call: (561) 768-0473 or email Greg Corbitt at gcorbitt@tequesta.org

Deadline Date for Proposals: 4/12/2021 by 2:00 PM